


Sky Stage Ultra Standard Platform

Sky Stage Ultra is a "third generation" modular platform that combines the best of current technology with new concepts. It is used in commercial restoration, painting, sandblasting, waterproofing, caulking, window cleaning, inspections, off-shore oil rigs, and general building maintenance. A Sky Stage Ultra Standard Platform system investment allows for unlimited configuration.

- 50 ft (15m) span between suspension points (only 2 hoists)
- 70 ft (21m) length is possible with addition of 2 Moveable Walk-thru Stirrups
- Reinforced, reversible floor panels provide the industry's most stable platform
- Solid floor available
- Added features for quick and safe erection and dismantling
- Adjustable handrails provide more versatility and more work surface access
- Top rail lock pin assembly to prevent accidental release and jamming
- Compatibility with other platforms in the industry afford fleet optimization
- Moveable Low-profile Stirrup
- Horizontal Hinge
- 0-90° Adjustable Corner
- Moveable Walk-thru Stirrup
- Modular design for easy storage, transport, and replacement
- · Lighter weight with wheels for easier movement
- Load rated up to 2000 lbs
- Dual wire rope capability
- Quick & easy installation that requires no tools
- 3 meter cantilever with use of moveable Walk-thru Stirrups
- Meets or exceeds all OSHA and ANSI standards
- UL Classified
- Multi-tier options with trap door floor
- · Permanent Installation capability
- Dance floor options

All Sky Stage Ultra Platform decals are available in Spanish. Part numbers and pricing are available by contacting customer service.

















Available in .5m, 1m, 1.5m, 2m, 3m

Size	Part No.	Wt.
.5m	361210	7 lbs
1m	361027	14 lbs
1.5m	361032	20 lbs
2m	361033	26 lbs
3m	361035	29 lbs







TOP RAIL ASSEMBLY

Available in .5m, 1m, 2m, & 3m

Size	Part No.	Wt.
.5m	360194	1.5 lbs
1m	360146	3 lbs
1.5m	360147	4 lbs
2m	360148	5 lbs
3m	360149	7 lbs

FLOOR PANEL (Deck)

Available in .5m, 1m, 1.5m, 2m, & 3m

Size	Part No.	Wt.						
.5m	360193	7 lbs						
1m	360040	15 lbs						
1.5m	360041	21 lbs						
2m	360042	27 lbs						
3m	360043	37 lbs						
* Solid floor available								

SKY STAGE		SAFE W	ORKING LOAD ONLY FOR CONFIGURATIONS WITH END STIRRU	IPS .		SKY STAGE	
Max. Safe Working Load (uniformly distributed) 2000 lbs (900 kg)	Suspension Distance	Self-Weight	Instructions for actual safe working load Add working load limit of hoists. Self-V	Weight	Suspension Distance	Max. Safe Working Load (uniformly	
	6'9" (2m)	249lbs (113kg)		(265kg)	(9m) 29'3"	distributed)	
(900 kg)	9' 9" (3m)	285lbs (129kg)		(300kg)	(10m) 33'0"	(450kg)	
	13'6" (4m)	363lbs (164kg)		(316kg)	(11m) 36'0"		
	16' 6" (5m)	399lbs (181kg)		(333kg)	(12m) 39'0"		
	19' 6" (6m)	435lbs (197kg)	prior to assembling. ATTACATACATACATACATACATACATACATACATACAT	(368kg)	(13m) 42'9"	750 lbs	
1500 lbs	23' 3" (7m)	512lbs (232kg)	2 3 2 3 3 3 847lbs	(384kg)	(14m) 45'9"	(340kg)	
(680 kg)	26' 3" (8m)	548lbs (249kg)	3 2 3 883lbs	(401kg)	(15m) 48'10'		

*Available in Multi-tier Options

SKY STAGE BY COMPONENT															
DESCRIPTION	PART NO.	2m	3m	4m	5m	6m	7m	8m	9m	10m	11m	12m	13m	14m	15m
Side Panel - 3 meter	360035	0	2	0	2	4	2	4	6	4	6	8	6	8	10
Side Panel - 2 meter	360033	2	0	4	2	0	4	2	0	4	2	0	4	2	0
Side Panel - 1 meter	360031	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Side Panel - 1.5 meter	360032														
Side Panel5 meter	360195														
Floor Panel - 3 meter	360043	0	1	0	1	2	1	2	3	2	3	4	3	4	5
Floor Panel - 2 meter	360042	1	0	2	1	0	2	1	0	2	1	0	2	1	0
Floor Panel - 1 meter	360040	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Floor Panel - 1.5 meter	360041														
Floor Panel5 meter	360193														
Top Rail Assembly - 3 meter	360149	0	2	0	2	4	2	4	6	4	6	8	6	8	10
Top Rail Assembly - 2 meter		2	0	4	2	0	4	2	0	4	2	0	4	2	0
Top Rail Assembly - 1meter	360146	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Top Rail Assembly - 1.5 meter	360147														
Top Rail Assembly5 meter	360194														
Connecting Frame	360039	2	2	3	3	3	4	4	4	5	5	5	6	6	6
Telescoping Post	360054	4	4	6	6	6	8	8	8	10	10	10	12	12	12
End Stirrup	360150	2	2	2	2	2	2	2	2	2	2	2	2	2	2
Caster Assembly	360065	4	4	4	4	4	4	4	4	4	4	4	4	4	4
Wall Roller	360111	2	2	2	2	2	2	2	2	2	2	2	2	2	2
Lock Pin	360019	16	16	30	30	30	44	44	44	58	58	58	72	72	72
Moveable Walk-Thru Stirrup	360130						variab	le			-, 170 0-0				
Moveable Walk-By Low Profile							variable								
Adjustable Corner	360100						variab								
Horizontal Hinge	360105						variab								
End Gate	360140						variab								